## HASSAN DISTRICT.

*Notification dated 7th February* 1929.

Notice is hereby given that sealed tenders will be received at the Office of the President, District Board, Hassan, up to 2 P.M. on Monday the 18th February 1929, for constructing an out house attached to the Musafirkhana at Channarayapatna. Approximate estimate of quantities are given below. The quantities are not guaranteed. The work should be completed before the close of the official year.

2. The plan, detailed estimate and conditions may be seen at the President's office at Hassan, between the hours of 11 A.M. and 5 P.M. on all working days.

3. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rs. 200 only in cash or Government Promissory notes as earnest money and be superscribed "Tender for constructing an out house to the Musafirkhana at Channarayapatna" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the President, District Board, Hassan, who does not bind himself to accept the lowest tender or to assign any reason whatsoever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the President's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenderers, the earnest money on rejected tenders will be returned.

Abstract estimate of probable quantity for the out house to the Musafirkhana at Channarayapatna.

| | Particulars | Per | Rate | Quantity | Cost | Total |
|---|---|---|---|---|---|---|
| | | | Rs. a. p. | | | |
| 1. | Earthwork excavation ... ... | Cyd. | | 16 | | |
| 2. | Rough stone in clay filling in foundation... | C.ft. | | 442 | | |
| 3. | Size stone in clay basement ... ... | " | | 331·87 | | |
| 4. | Burnt brick in clay ... ... | " | | 927·60 | | |
| 5. | Burnt brick in mortar ... ... | " | | 222·23 | | |
| 6. | Honne or Naadi wood ... ... | " | | 62·66 | | |
| 7. | First class Mangalore tiles roofing over teak rafters. | Sqr. | | 9·12 | | |
| 8. | Honne or Naadi wood doors with shutters | S.ft. | | 137·50 | | |
| 9. | Do do windows with shutters iron bars, etc., complete. | " | | 41·50 | | |
| 10. | Ventilator with shutters of expanded metal | " | | 8·75 | | |
| 11. | Burnt stone slabs 3" to 4" thick ... | " | | 183·75 | | |
| 12. | Teakwood pegs ... ... | No. | | 10 | | |
| 13. | Mortar plastering ... ... | Sqrs. | | 20·04 | | |
| 14. | Chacolate painting ... ... | " | | 4·00 | | |
| 15. | Mortar pointing to basement... ... | " | | 1·72 | | |
| 16. | Earth filling to basement ... ... | C.yd. | | 18 | | |
| 17. | Flooring with 1st class Mangalore tiles over 3" concrete with cement pointing. | Sqrs. | | 4·56 | | |
| 18. | Constructing bath sink with stone slabs 5" 6" well dressed, etc. | L. S. | | ... | | |
| 19. | Constructing arch over kitchen oven with burnt brick in mortar and cement plastering. | L. S. | | ... | | |
| 20. | Constructing oath oven ... ... | L. S. | | ... | | |
| 21. | Inserting zinc pipe of 6" diameter meter to lead off smoke. | R.ft. | | 24 | | |
| 22. | Mortar and pedie ... ... | No | | 1 | | |
| 23. | Smoke vent tile ... ... | " | | 4 | | |
| 24. | Contingencies ... ... ... | L. S. | | ... | | |
| 25. | Ridge tiles set in mortar ... ... | R.ft. | | 38 | | |
| 26. | Chunam borders... ... ... | " | | 44 | | |
| 27. | Adjusting the old kitchen roofing wirh that of the new one, etc. | L. S. | | ... | | |
| 28. | Eve Board of Honne wood 9" | S.ft. | | 98 | | |